

Marblehead Conservation Commission
Minutes November 12, 2020

Meeting was held remotely in accordance with Governor Baker's March 12, 2020 Order Superseding Certain Provisions of the Open Meeting Law, G.L. c.30A, section 18 and the Governor's March 15, 2020 Order imposing strict limitation on the number of people that may gather in one place.

Meeting was called to order at 7:00 PM

Present were: Commission Members Brian LeClair, Michael Smith, William Colehower, and David VanHoven. Also present was Conservation Administrator and Town Engineer, Charles Quigley.

The hearings were conducted under the Massachusetts Wetlands Protection Act and the Marblehead Wetlands Protection Bylaw.

Note: The commission currently has six members. Per the MACC Handbook, section 4.1.2, most lawyers agree that a quorum is "...a majority of commissioners currently serving". The quorum for this meeting is therefore four members.

DISCUSSIONS:

- **Conservancy** – Don Morgan – report from the Marblehead Conservancy Group and a question about adding gravel to the Steer Swamp entrance at Beacon Street. All members agreed to proceed.
- **Bike Marblehead** – Pat Milner – discuss potential bicycle pump track locations – see presentation submitted. 54 Evans Road Andrew Petty spoke in favor and offered Town assistance.

Certificate of Compliance Request

- **40-1255 Riverhead Beach** – Town of Marblehead – annual tree burning. Commission voted to approve unanimously and amend COC to have a surviving condition to allow annual tree burning subject to the original order of conditions.
- **40-67 4 Broadmere** – Stephan Thompson et ux – pier work . The Commission voted unanimously to approve.
- **40-1270 10 Mooring Rd** – new house & site work. The Commission voted unanimously to approve.
- **40-1271 33 Bradlee Rd** – new pool & site work. The Commission voted unanimously to approve.
- **40-708 4 Harbor View** – John Hasset – sitework. The Commission voted unanimously to approve.
- **40-1296 1 Flint St** – Greg Birtwell - landscaping. The Commission voted unanimously to approve.

MINOR MODIFICATION REQUEST:

40-950 11 Neptune Rd – James Kaloutas – landscaping. Kathy Bradford appeared and the submitted 10/22/20 letter was presented. The Commission voted to continue.

40-1406 293R Ocean Ave- Peter Noyes – stairway, decks added/modified – Peter Ogren appeared and presented the 10/28/2020 by Hayes Engineering Plan to Accompany NOI #293R Ocean Ave plan with added drywall 4' diameter with crushed stone required to be submitted, The Commission voted unanimously to approve.

40-1405 61 Naugus Ave – Alan November – pier, landing - The Commission voted to continue.

ORDER OF CONDITIONS EXTENSION REQUEST:

40-1295 147 Front Street – David Francis – rehab decks and façade. The Commission voted unanimously to approve.

HEARINGS:

NOI 40-1395 313 Ocean Ave – Kazim Bayus

Appeared: Peter Ogren, Haye's Engineering

Proposed: Amendment to an existing Order of Conditions – Landscaping

Applicant withdrew remaining amendment request.

NOI 40-1454 41 Orchard Street – Patrick & Jennifer Duffy

Appeared: Scott Patrowicz, Patrowicz Land Development Engineering

Proposed: Swimming Pool.

Control Drawing: Plan Changes from Permitted verses Proposed dated October 20, 2020 by Patrowicz Engineers

All members voted to close the hearing. Three (3) members voted to issue an OOC and one (1) member voted against with the following special conditions:

33. There shall be no cleaning or rinsing of cement concrete ready-mix trucks, or cement concrete mixing equipment, such that the byproduct of the cleaning or rinsing operation finds its way to any resource area by any means, especially, but not limited to, by means of a storm drainage system (catch basins, pipes, drainage ditches, etc.).

34. To the maximum extent possible, all driveways, terraces, patios or similar ground-level surfaces shall be constructed as permeable surfaces to allow water to infiltrate through their surfaces into the ground on site.

36. All construction material shall be stored outside the resource area and its buffer zone or as far back from the resource areas as possible.

40. By voluntary agreement with the applicant, only organic fertilizers are to be used on the property landward of the resource areas. Fertilizers should not contain pesticides or herbicides; should contain slow release nitrogen and should not contain more than 3% phosphorous. To mitigate chemical runoff, do not fertilize directly before a rainstorm and do not over fertilize.

Apply fertilizer in late April and in September (refer to: A Homeowner's Guide to Environmentally Sound Lawn care published by the Massachusetts Department of Food and Agriculture and the booklet, Don't Trash Grass, published by the Massachusetts Department of Environmental Protection). **This condition shall survive this order.**

45. When a pool/spa/hot tub is to be drained, no chlorine or other chemicals are to be added to the pool water for a period of at least four (4) days prior to draining to allow for the chlorine and other chemicals to dissipate; and there shall be an appropriate sign placed permanently at or immediately adjacent to the pool/spa/hot tub drainage valve or mechanism indicating this requirement. The method of pool drainage shall be such as to prevent any soil erosion by the draining water and to allow the draining water to seep into the ground prior to entering any resource waters. No direct discharge to resource waters is allowed. **This condition shall survive this order.**

50. Invasive plants shall not be used nor maintained in the landscape of the project site. This applies to the existing landscape as well as to any proposed landscape. A list of invasive plants in Massachusetts can be found in the latest update of The Evaluation of Non-Native Plant Species for Invasiveness in Massachusetts (with annotated list) produced by the Massachusetts Invasive Plant Advisory Group. For most recent update, visit www.mnla.com or www.newfs.org. **This condition shall survive this order.**

55. Upon completion of the work allowed under this Order of Conditions the applicant shall apply for a Certificate of Compliance (COC) (a) within 30 days after completion of the work or (b) thirty (30) days prior to the expiration date of the original or extended OOC, whichever time comes sooner. If no work was started under the OOC or if some of the work will not be performed, the applicant must still apply for a Certificate of Compliance at least 30 days prior to the expiration of the OOC. The Conservation Commission may require the submission of an "as built" drawing (signed and stamped by a licensed Professional Engineer or licensed Professional Land Surveyor) with the application for the COC. Failure to submit an application for a COC shall result in a fine issued against the applicant in accordance with Marblehead Bylaws Chapter 194, Section 11E. **See Attachment "C" for "Schedule of Fines".**

NOI 40-1458 24 Nonantum Rd – Paul Murphy.

Appeared: John Dick

Proposed: Masonry and wall repairs.

Control Drawing: See plans accompanying application.

Applicant presented plans as provided in application.

All members voted to close the hearing. All members voted to issue an OOC with the following special conditions:

33. There shall be no cleaning or rinsing of cement concrete ready-mix trucks, or cement concrete mixing equipment, such that the byproduct of the cleaning or rinsing operation finds its way to any resource area by any means, especially, but not limited to, by means of a storm drainage system (catch basins, pipes, drainage ditches, etc.).

34. To the maximum extent possible, all driveways, terraces, patios or similar ground-level surfaces shall be constructed as permeable surfaces to allow water to infiltrate through their surfaces into the ground on site.

35. All demolition debris shall be removed from the site as soon as possible and not stored within a resource area or a buffer zone. If a dumpster is used to contain debris, the dumpster shall be covered after each work day. The debris shall be properly disposed of in accordance with applicable federal, state and local regulations.

36. All construction material shall be stored outside the resource area and its buffer zone or as far back from the resource areas as possible.

40. By voluntary agreement with the applicant, only organic fertilizers are to be used on the property landward of the resource areas. Fertilizers should not contain pesticides or herbicides; should contain slow release nitrogen and should not contain more than 3% phosphorous. To mitigate chemical runoff, do not fertilize directly before a rainstorm and do not over fertilize. Apply fertilizer in late April and in September (refer to: A Homeowner's Guide to Environmentally Sound Lawn care published by the Massachusetts Department of Food and Agriculture and the booklet, Don't Trash Grass, published by the Massachusetts Department of Environmental Protection). **This condition shall survive this order.**

41. Maintenance pointing and repairs of existing stone masonry walls and concrete walls including the replacement of an occasional missing stone or patching cracks and minor defects in a concrete wall are allowed as a surviving condition to this Order of Conditions. **The property owner shall inform the Conservation Commission in writing at least seven days prior to any proposed repointing or repair work on existing walls.** All dislodged and removed mortar/cement will be immediately contained and removed from the work site to prevent any such material from entering the resource waters. Any future razing, rebuilding or enlarging of the subject wall(s) will require the filing of a new Notice of Intent. **This condition shall survive this order.**

42. The repair/replacement of small sections of damaged caps on seawalls is allowed as a surviving condition. All dislodged and removed caps will be immediately contained and removed from the work site to prevent any such material from entering the resource waters. Prior to any work, the scope of the proposed repair/replacement must be approved by the Conservation Commission. If the cap on a major length or on an entire wall needs to be repaired/replaced, this requires an NOI. **This condition shall survive this order.**

44. The back-filling of small areas of erosion landward of a seawall is allowed as a surviving condition provided the erosion is not on a coastal bank. This back-filling applies to areas defined primarily as Land Subject to Coastal Storm Flowage. Any work on a coastal bank requires an NOI. The back-fill material must be clean and compatible with the eroded material. Prior to any back-filling, the scope of the proposed back-filling must be approved by the Conservation Commission. **This condition shall survive this order.**

50. Invasive plants shall not be used nor maintained in the landscape of the project site. This applies to the existing landscape as well as to any proposed landscape. A list of invasive plants in Massachusetts can be found in the latest update of The Evaluation of Non-Native Plant Species

for Invasiveness in Massachusetts (with annotated list) produced by the Massachusetts Invasive Plant Advisory Group. For most recent update, visit www.mnla.com or www.newfs.org. **This condition shall survive this order.**

55. Upon completion of the work allowed under this Order of Conditions the applicant shall apply for a Certificate of Compliance (COC) (a) within 30 days after completion of the work or (b) thirty (30) days prior to the expiration date of the original or extended OOC, whichever time comes sooner. If no work was started under the OOC or if some of the work will not be performed, the applicant must still apply for a Certificate of Compliance at least 30 days prior to the expiration of the OOC. The Conservation Commission may require the submission of an "as built" drawing (signed and stamped by a licensed Professional Engineer or licensed Professional Land Surveyor) with the application for the COC. Failure to submit an application for a COC shall result in a fine issued against the applicant in accordance with Marblehead Bylaws Chapter 194, Section 11E. **See Attachment "C" for "Schedule of Fines".**

102. A tarp will be laid down at the base of the seawall during all repair work to capture all construction debris. The tarp will be on the seaward side of the seawall. The tarp will be rolled up and dumped into a disposal trailer as required throughout the work day and will be removed at the end of each work day.

105. Tarps shall be spread and secured over the work area on top of the existing resource area for debris containment and collection during low to medium tides. The tarps and debris will be removed between tides and at the end of workday. At no time are the tarps to be inundated due to rain, tidal or wave action. The tarps are to be removed no less than ½ hour prior to expected inundation. At that time all work is to cease in the area near the resource area.

NOI 40-1465 101 Bubier Rd – Peter Hart

Appeared: John Dick

Proposed: Tree removal.

Control Drawing: See plans accompanying application.

Applicant presented plans as provided in application.

All members voted to close the hearing. All members voted to issue an OOC with the following special conditions:

40. By voluntary agreement with the applicant, only organic fertilizers are to be used on the property landward of the resource areas. Fertilizers should not contain pesticides or herbicides; should contain slow release nitrogen and should not contain more than 3% phosphorous. To mitigate chemical runoff, do not fertilize directly before a rainstorm and do not over fertilize. Apply fertilizer in late April and in September (refer to: A Homeowner's Guide to Environmentally Sound Lawn care published by the Massachusetts Department of Food and Agriculture and the booklet, Don't Trash Grass, published by the Massachusetts Department of Environmental Protection). **This condition shall survive this order.**

50. Invasive plants shall not be used nor maintained in the landscape of the project site. This

applies to the existing landscape as well as to any proposed landscape. A list of invasive plants in Massachusetts can be found in the latest update of The Evaluation of Non-Native Plant Species for Invasiveness in Massachusetts (with annotated list) produced by the Massachusetts Invasive Plant Advisory Group. For most recent update, visit www.mnla.com or www.newfs.org. **This condition shall survive this order.**

55. Upon completion of the work allowed under this Order of Conditions the applicant shall apply for a Certificate of Compliance (COC) (a) within 30 days after completion of the work or (b) thirty (30) days prior to the expiration date of the original or extended OOC, whichever time comes sooner. If no work was started under the OOC or if some of the work will not be performed, the applicant must still apply for a Certificate of Compliance at least 30 days prior to the expiration of the OOC. The Conservation Commission may require the submission of an "as built" drawing (signed and stamped by a licensed Professional Engineer or licensed Professional Land Surveyor) with the application for the COC. Failure to submit an application for a COC shall result in a fine issued against the applicant in accordance with Marblehead Bylaws Chapter 194, Section 11E. **See Attachment "C" for "Schedule of Fines"**.

NOI 40-1457 90 Seaview - Courtney Lobraico.

Appeared: Peter Ogren Haye's Engineering

Proposed: Swimming Pool.

Control Drawing: Plan to Accompany Notice of Intent #90 Seaview Ave dated 9/23/20 by Haye's Engineering.

Applicant presented plans as provided in application.

All members voted to close the hearing. All members voted to issue an OOC with the following special conditions:

33. There shall be no cleaning or rinsing of cement concrete ready-mix trucks, or cement concrete mixing equipment, such that the byproduct of the cleaning or rinsing operation finds its way to any resource area by any means, especially, but not limited to, by means of a storm drainage system (catch basins, pipes, drainage ditches, etc.).

34. To the maximum extent possible, all driveways, terraces, patios or similar ground-level surfaces shall be constructed as permeable surfaces to allow water to infiltrate through their surfaces into the ground on site.

36. All construction material shall be stored outside the resource area and its buffer zone or as far back from the resource areas as possible.

40. By voluntary agreement with the applicant, only organic fertilizers are to be used on the property landward of the resource areas. Fertilizers should not contain pesticides or herbicides; should contain slow release nitrogen and should not contain more than 3% phosphorous. To mitigate chemical runoff, do not fertilize directly before a rainstorm and do not over fertilize. Apply fertilizer in late April and in September (refer to: A Homeowner's Guide to Environmentally Sound Lawn care published by the Massachusetts Department of Food and Agriculture and the booklet, Don't Trash Grass, published by the Massachusetts Department of

Environmental Protection). **This condition shall survive this order.**

45. When a pool/spa/hot tub is to be drained, no chlorine or other chemicals are to be added to the pool water for a period of at least four (4) days prior to draining to allow for the chlorine and other chemicals to dissipate; and there shall be an appropriate sign placed permanently at or immediately adjacent to the pool/spa/hot tub drainage valve or mechanism indicating this requirement. The method of pool drainage shall be such as to prevent any soil erosion by the draining water and to allow the draining water to seep into the ground prior to entering any resource waters. No direct discharge to resource waters is allowed. **This condition shall survive this order.**

50. Invasive plants shall not be used nor maintained in the landscape of the project site. This applies to the existing landscape as well as to any proposed landscape. A list of invasive plants in Massachusetts can be found in the latest update of The Evaluation of Non-Native Plant Species for Invasiveness in Massachusetts (with annotated list) produced by the Massachusetts Invasive Plant Advisory Group. For most recent update, visit www.mnla.com or www.newfs.org. **This condition shall survive this order.**

55. Upon completion of the work allowed under this Order of Conditions the applicant shall apply for a Certificate of Compliance (COC) (a) within 30 days after completion of the work or (b) thirty (30) days prior to the expiration date of the original or extended OOC, whichever time comes sooner. If no work was started under the OOC or if some of the work will not be performed, the applicant must still apply for a Certificate of Compliance at least 30 days prior to the expiration of the OOC. The Conservation Commission may require the submission of an "as built" drawing (signed and stamped by a licensed Professional Engineer or licensed Professional Land Surveyor) with the application for the COC. Failure to submit an application for a COC shall result in a fine issued against the applicant in accordance with Marblehead Bylaws Chapter 194, Section 11E. **See Attachment "C" for "Schedule of Fines".**

NOI 40-1462 6 Broadmere Way – Richard & Elaine Spenceley.

Appeared: Scott Patrowicz, Patrowicz Land Development Engineering

Proposed: Seawall-revetment repairs & site work.

Control Drawing: Site plan #6 Broadmere Way dated 10/23/20 by Patrowicz Engineering.

Applicant presented plans as provided in application.

All members voted to close the hearing. All members voted to issue an OOC with the following special conditions:

33. There shall be no cleaning or rinsing of cement concrete ready-mix trucks, or cement concrete mixing equipment, such that the byproduct of the cleaning or rinsing operation finds its way to any resource area by any means, especially, but not limited to, by means of a storm drainage system (catch basins, pipes, drainage ditches, etc.).

34. To the maximum extent possible, all driveways, terraces, patios or similar ground-level surfaces shall be constructed as permeable surfaces to allow water to infiltrate through their surfaces into the ground on site.

35. All demolition debris shall be removed from the site as soon as possible and not stored within a resource area or a buffer zone. If a dumpster is used to contain debris, the dumpster shall be covered after each work day. The debris shall be properly disposed of in accordance with applicable federal, state and local regulations.

36. All construction material shall be stored outside the resource area and its buffer zone or as far back from the resource areas as possible.

40. By voluntary agreement with the applicant, only organic fertilizers are to be used on the property landward of the resource areas. Fertilizers should not contain pesticides or herbicides; should contain slow release nitrogen and should not contain more than 3% phosphorous. To mitigate chemical runoff, do not fertilize directly before a rainstorm and do not over fertilize. Apply fertilizer in late April and in September (refer to: A Homeowner's Guide to Environmentally Sound Lawn care published by the Massachusetts Department of Food and Agriculture and the booklet, Don't Trash Grass, published by the Massachusetts Department of Environmental Protection). **This condition shall survive this order.**

41. Maintenance pointing and repairs of existing stone masonry walls and concrete walls including the replacement of an occasional missing stone or patching cracks and minor defects in a concrete wall are allowed as a surviving condition to this Order of Conditions. **The property owner shall inform the Conservation Commission in writing at least seven days prior to any proposed repointing or repair work on existing walls.** All dislodged and removed mortar/cement will be immediately contained and removed from the work site to prevent any such material from entering the resource waters. Any future razing, rebuilding or enlarging of the subject wall(s) will require the filing of a new Notice of Intent. **This condition shall survive this order.**

42. The repair/replacement of small sections of damaged caps on seawalls is allowed as a surviving condition. All dislodged and removed caps will be immediately contained and removed from the work site to prevent any such material from entering the resource waters. Prior to any work, the scope of the proposed repair/replacement must be approved by the Conservation Commission. If the cap on a major length or on an entire wall needs to be repaired/replaced, this requires an NOI. **This condition shall survive this order.**

43. When the repair of a seawall entails the use of existing rip-rap which was previously located at the toe of the seawall but has been distributed onto the beach seaward of the seawall by wave action, the following applies. The rip-rap lying above the mean high tide line can be re-located to the toe of the seawall. The rip-rap lying at or below the mean high tide line cannot be disturbed. This special condition is not a surviving condition and is valid only for that work specified for this particular application. **The property owner shall inform the Conservation Commission in writing at least seven days prior to any proposed repair work on an existing existing riprap revetment.**

50. Invasive plants shall not be used nor maintained in the landscape of the project site. This applies to the existing landscape as well as to any proposed landscape. A list of invasive plants in Massachusetts can be found in the latest update of The Evaluation of Non-Native Plant Species for Invasiveness in Massachusetts (with annotated list) produced by the Massachusetts Invasive

Plant Advisory Group. For most recent update, visit www.mnla.com or www.newfs.org. **This condition shall survive this order.**

55. Upon completion of the work allowed under this Order of Conditions the applicant shall apply for a Certificate of Compliance (COC) (a) within 30 days after completion of the work or (b) thirty (30) days prior to the expiration date of the original or extended OOC, whichever time comes sooner. If no work was started under the OOC or if some of the work will not be performed, the applicant must still apply for a Certificate of Compliance at least 30 days prior to the expiration of the OOC. The Conservation Commission may require the submission of an "as built" drawing (signed and stamped by a licensed Professional Engineer or licensed Professional Land Surveyor) with the application for the COC. Failure to submit an application for a COC shall result in a fine issued against the applicant in accordance with Marblehead Bylaws Chapter 194, Section 11E. **See Attachment "C" for "Schedule of Fines".**

102. A tarp will be laid down at the base of the seawall during all repair work to capture all construction debris. The tarp will be on the seaward side of the seawall. The tarp will be rolled up and dumped into a disposal trailer as required throughout the work day and will be removed at the end of each work day.

105. Tarps shall be spread and secured over the work area on top of the existing resource area for debris containment and collection during low to medium tides. The tarps and debris will be removed between tides and at the end of workday. At no time are the tarps to be inundated due to rain, tidal or wave action. The tarps are to be removed no less than ½ hour prior to expected inundation. At that time all work is to cease in the area near the resource area.

107. Before any landscape work begins, the applicant shall submit a landscape plan to the Commission for approval. No landscape work may commence until the Commission has approved the landscape plan.

XXX. No equipment is permitted in the intertidal area.

NOI 40-1459 325 Ocean Avenue – Serpentine Holdings, LLC.

Appeared: Scott Patrowicz, Patrowicz Land Development Engineering

Proposed: Seawall repairs & site work.

Control Drawing: Site Plan #325 Ocean Ave dated 10/21/2020 by Patrowicz Engineering.

Applicant presented plans as provided in application.

All members voted to close the hearing. All members voted to issue an OOC with the following special conditions:

33. There shall be no cleaning or rinsing of cement concrete ready-mix trucks, or cement concrete mixing equipment, such that the byproduct of the cleaning or rinsing operation finds its way to any resource area by any means, especially, but not limited to, by means of a storm drainage system (catch basins, pipes, drainage ditches, etc.).

34. To the maximum extent possible, all driveways, terraces, patios or similar ground-level

surfaces shall be constructed as permeable surfaces to allow water to infiltrate through their surfaces into the ground on site.

35. All demolition debris shall be removed from the site as soon as possible and not stored within a resource area or a buffer zone. If a dumpster is used to contain debris, the dumpster shall be covered after each work day. The debris shall be properly disposed of in accordance with applicable federal, state and local regulations.

36. All construction material shall be stored outside the resource area and its buffer zone or as far back from the resource areas as possible.

40. By voluntary agreement with the applicant, only organic fertilizers are to be used on the property landward of the resource areas. Fertilizers should not contain pesticides or herbicides; should contain slow release nitrogen and should not contain more than 3% phosphorous. To mitigate chemical runoff, do not fertilize directly before a rainstorm and do not over fertilize. Apply fertilizer in late April and in September (refer to: A Homeowner's Guide to Environmentally Sound Lawn care published by the Massachusetts Department of Food and Agriculture and the booklet, Don't Trash Grass, published by the Massachusetts Department of Environmental Protection). **This condition shall survive this order.**

41. Maintenance pointing and repairs of existing stone masonry walls and concrete walls including the replacement of an occasional missing stone or patching cracks and minor defects in a concrete wall are allowed as a surviving condition to this Order of Conditions. **The property owner shall inform the Conservation Commission in writing at least seven days prior to any proposed repointing or repair work on existing walls.** All dislodged and removed mortar/cement will be immediately contained and removed from the work site to prevent any such material from entering the resource waters. Any future razing, rebuilding or enlarging of the subject wall(s) will require the filing of a new Notice of Intent. **This condition shall survive this order.**

42. The repair/replacement of small sections of damaged caps on seawalls is allowed as a surviving condition. All dislodged and removed caps will be immediately contained and removed from the work site to prevent any such material from entering the resource waters. Prior to any work, the scope of the proposed repair/replacement must be approved by the Conservation Commission. If the cap on a major length or on an entire wall needs to be repaired/replaced, this requires an NOI. **This condition shall survive this order.**

43. When the repair of a seawall entails the use of existing rip-rap which was previously located at the toe of the seawall but has been distributed onto the beach seaward of the seawall by wave action, the following applies. The rip-rap lying above the mean high tide line can be re-located to the toe of the seawall. The rip-rap lying at or below the mean high tide line cannot be disturbed. This special condition is not a surviving condition and is valid only for that work specified for this particular application. **The property owner shall inform the Conservation Commission in writing at least seven days prior to any proposed repair work on an existing existing riprap revetment.**

50. Invasive plants shall not be used nor maintained in the landscape of the project site. This applies to the existing landscape as well as to any proposed landscape. A list of invasive plants in

Massachusetts can be found in the latest update of The Evaluation of Non-Native Plant Species for Invasiveness in Massachusetts (with annotated list) produced by the Massachusetts Invasive Plant Advisory Group. For most recent update, visit www.mnla.com or www.newfs.org. **This condition shall survive this order.**

55. Upon completion of the work allowed under this Order of Conditions the applicant shall apply for a Certificate of Compliance (COC) (a) within 30 days after completion of the work or (b) thirty (30) days prior to the expiration date of the original or extended OOC, whichever time comes sooner. If no work was started under the OOC or if some of the work will not be performed, the applicant must still apply for a Certificate of Compliance at least 30 days prior to the expiration of the OOC. The Conservation Commission may require the submission of an "as built" drawing (signed and stamped by a licensed Professional Engineer or licensed Professional Land Surveyor) with the application for the COC. Failure to submit an application for a COC shall result in a fine issued against the applicant in accordance with Marblehead Bylaws Chapter 194, Section 11E. **See Attachment "C" for "Schedule of Fines".**

102. A tarp will be laid down at the base of the seawall during all repair work to capture all construction debris. The tarp will be on the seaward side of the seawall. The tarp will be rolled up and dumped into a disposal trailer as required throughout the work day and will be removed at the end of each work day.

105. Tarps shall be spread and secured over the work area on top of the existing resource area for debris containment and collection during low to medium tides. The tarps and debris will be removed between tides and at the end of workday. At no time are the tarps to be inundated due to rain, tidal or wave action. The tarps are to be removed no less than ½ hour prior to expected inundation. At that time all work is to cease in the area near the resource area.

109. Petitioner shall not place stones or other materials on the property of others without the prior written permission of the relevant property owner.

XXX. Ledge will not be permitted to be hammered.

NOI 40-1461 3 Driftwood Road – Stephanie & Andrew Katz.

Appeared: Scott Patrowicz, Patrowicz Land Development Engineering

Proposed: Garage, house, deck additions and repairs & site work.

Control Drawing: Site Plan # 3 Driftwood dated 10/23/2020 by Patrowicz Engineering.

Applicant presented plans as provided in application.

All members voted to close the hearing. All members voted to issue an OOC with the following special conditions:

33. There shall be no cleaning or rinsing of cement concrete ready-mix trucks, or cement concrete mixing equipment, such that the byproduct of the cleaning or rinsing operation finds its way to any resource area by any means, especially, but not limited to, by means of a storm drainage system (catch basins, pipes, drainage ditches, etc.).

34. To the maximum extent possible, all driveways, terraces, patios or similar ground-level surfaces shall be constructed as permeable surfaces to allow water to infiltrate through their surfaces into the ground on site.

35. All demolition debris shall be removed from the site as soon as possible and not stored within a resource area or a buffer zone. If a dumpster is used to contain debris, the dumpster shall be covered after each work day. The debris shall be properly disposed of in accordance with applicable federal, state and local regulations.

36. All construction material shall be stored outside the resource area and its buffer zone or as far back from the resource areas as possible.

40. By voluntary agreement with the applicant, only organic fertilizers are to be used on the property landward of the resource areas. Fertilizers should not contain pesticides or herbicides; should contain slow release nitrogen and should not contain more than 3% phosphorous. To mitigate chemical runoff, do not fertilize directly before a rainstorm and do not over fertilize. Apply fertilizer in late April and in September (refer to: A Homeowner's Guide to Environmentally Sound Lawn care published by the Massachusetts Department of Food and Agriculture and the booklet, Don't Trash Grass, published by the Massachusetts Department of Environmental Protection). **This condition shall survive this order.**

50. Invasive plants shall not be used nor maintained in the landscape of the project site. This applies to the existing landscape as well as to any proposed landscape. A list of invasive plants in Massachusetts can be found in the latest update of The Evaluation of Non-Native Plant Species for Invasiveness in Massachusetts (with annotated list) produced by the Massachusetts Invasive Plant Advisory Group. For most recent update, visit www.mnla.com or www.newfs.org. **This condition shall survive this order.**

55. Upon completion of the work allowed under this Order of Conditions the applicant shall apply for a Certificate of Compliance (COC) (a) within 30 days after completion of the work or (b) thirty (30) days prior to the expiration date of the original or extended OOC, whichever time comes sooner. If no work was started under the OOC or if some of the work will not be performed, the applicant must still apply for a Certificate of Compliance at least 30 days prior to the expiration of the OOC. The Conservation Commission may require the submission of an "as built" drawing (signed and stamped by a licensed Professional Engineer or licensed Professional Land Surveyor) with the application for the COC. Failure to submit an application for a COC shall result in a fine issued against the applicant in accordance with Marblehead Bylaws Chapter 194, Section 11E. **See Attachment "C" for "Schedule of Fines"**.

NOI 40-1460 4 Foster Street – Don & Noel Henrich.

Appeared: Scott Patrowicz, Patrowicz Land Development Engineering

Proposed: Garage additions, pool deck replacement & site work.

Control Drawing: Site Plan #4 Foster Street dated 10/26/2020 by Patrowicz Engineering.

Applicant presented plans as provided in application.

All members voted to close the hearing. All members voted to issue an OOC with the following special conditions:

33. There shall be no cleaning or rinsing of cement concrete ready-mix trucks, or cement concrete mixing equipment, such that the byproduct of the cleaning or rinsing operation finds its way to any resource area by any means, especially, but not limited to, by means of a storm drainage system (catch basins, pipes, drainage ditches, etc.).

34. To the maximum extent possible, all driveways, terraces, patios or similar ground-level surfaces shall be constructed as permeable surfaces to allow water to infiltrate through their surfaces into the ground on site.

35. All demolition debris shall be removed from the site as soon as possible and not stored within a resource area or a buffer zone. If a dumpster is used to contain debris, the dumpster shall be covered after each work day. The debris shall be properly disposed of in accordance with applicable federal, state and local regulations.

36. All construction material shall be stored outside the resource area and its buffer zone or as far back from the resource areas as possible.

40. By voluntary agreement with the applicant, only organic fertilizers are to be used on the property landward of the resource areas. Fertilizers should not contain pesticides or herbicides; should contain slow release nitrogen and should not contain more than 3% phosphorous. To mitigate chemical runoff, do not fertilize directly before a rainstorm and do not over fertilize. Apply fertilizer in late April and in September (refer to: A Homeowner's Guide to Environmentally Sound Lawn care published by the Massachusetts Department of Food and Agriculture and the booklet, Don't Trash Grass, published by the Massachusetts Department of Environmental Protection). **This condition shall survive this order.**

50. Invasive plants shall not be used nor maintained in the landscape of the project site. This applies to the existing landscape as well as to any proposed landscape. A list of invasive plants in Massachusetts can be found in the latest update of The Evaluation of Non-Native Plant Species for Invasiveness in Massachusetts (with annotated list) produced by the Massachusetts Invasive Plant Advisory Group. For most recent update, visit www.mnla.com or www.newfs.org. **This condition shall survive this order.**

55. Upon completion of the work allowed under this Order of Conditions the applicant shall apply for a Certificate of Compliance (COC) (a) within 30 days after completion of the work or (b) thirty (30) days prior to the expiration date of the original or extended OOC, whichever time comes sooner. If no work was started under the OOC or if some of the work will not be performed, the applicant must still apply for a Certificate of Compliance at least 30 days prior to the expiration of the OOC. The Conservation Commission may require the submission of an "as built" drawing (signed and stamped by a licensed Professional Engineer or licensed Professional Land Surveyor) with the application for the COC. Failure to submit an application for a COC shall result in a fine issued against the applicant in accordance with Marblehead Bylaws Chapter 194, Section 11E. **See Attachment "C" for "Schedule of Fines".**

NOI 40-1463 50C Cloutman's Lane – Barry & Julie Kelly.

Appeared: Scott Patrowicz, Patrowicz Land Development Engineering
Proposed: New house, seawall repairs & site work.

Control Drawing: Site Plan #50C Cloutman's Lane dated 10/25/2020 by Patrowicz Engineering.

Applicant presented plans as provided in application.

All members voted to close the hearing. All members voted to issue an OOC with the following special conditions:

33. There shall be no cleaning or rinsing of cement concrete ready-mix trucks, or cement concrete mixing equipment, such that the byproduct of the cleaning or rinsing operation finds its way to any resource area by any means, especially, but not limited to, by means of a storm drainage system (catch basins, pipes, drainage ditches, etc.).

34. To the maximum extent possible, all driveways, terraces, patios or similar ground-level surfaces shall be constructed as permeable surfaces to allow water to infiltrate through their surfaces into the ground on site.

35. All demolition debris shall be removed from the site as soon as possible and not stored within a resource area or a buffer zone. If a dumpster is used to contain debris, the dumpster shall be covered after each work day. The debris shall be properly disposed of in accordance with applicable federal, state and local regulations.

36. All construction material shall be stored outside the resource area and its buffer zone or as far back from the resource areas as possible.

40. By voluntary agreement with the applicant, only organic fertilizers are to be used on the property landward of the resource areas. Fertilizers should not contain pesticides or herbicides; should contain slow release nitrogen and should not contain more than 3% phosphorous. To mitigate chemical runoff, do not fertilize directly before a rainstorm and do not over fertilize. Apply fertilizer in late April and in September (refer to: A Homeowner's Guide to Environmentally Sound Lawn care published by the Massachusetts Department of Food and Agriculture and the booklet, Don't Trash Grass, published by the Massachusetts Department of Environmental Protection). **This condition shall survive this order.**

41. Maintenance pointing and repairs of existing stone masonry walls and concrete walls including the replacement of an occasional missing stone or patching cracks and minor defects in a concrete wall are allowed as a surviving condition to this Order of Conditions. **The property owner shall inform the Conservation Commission in writing at least seven days prior to any proposed repointing or repair work on existing walls.** All dislodged and removed mortar/cement will be immediately contained and removed from the work site to prevent any such material from entering the resource waters. Any future razing, rebuilding or enlarging of the subject wall(s) will require the filing of a new Notice of Intent. **This condition shall survive this order.**

42. The repair/replacement of small sections of damaged caps on seawalls is allowed as a surviving condition. All dislodged and removed caps will be immediately contained and

removed from the work site to prevent any such material from entering the resource waters. Prior to any work, the scope of the proposed repair/replacement must be approved by the Conservation Commission. If the cap on a major length or on an entire wall needs to be repaired/replaced, this requires an NOI. **This condition shall survive this order.**

50. Invasive plants shall not be used nor maintained in the landscape of the project site. This applies to the existing landscape as well as to any proposed landscape. A list of invasive plants in Massachusetts can be found in the latest update of The Evaluation of Non-Native Plant Species for Invasiveness in Massachusetts (with annotated list) produced by the Massachusetts Invasive Plant Advisory Group. For most recent update, visit www.mnla.com or www.newfs.org. **This condition shall survive this order.**

55. Upon completion of the work allowed under this Order of Conditions the applicant shall apply for a Certificate of Compliance (COC) (a) within 30 days after completion of the work or (b) thirty (30) days prior to the expiration date of the original or extended OOC, whichever time comes sooner. If no work was started under the OOC or if some of the work will not be performed, the applicant must still apply for a Certificate of Compliance at least 30 days prior to the expiration of the OOC. The Conservation Commission may require the submission of an "as built" drawing (signed and stamped by a licensed Professional Engineer or licensed Professional Land Surveyor) with the application for the COC. Failure to submit an application for a COC shall result in a fine issued against the applicant in accordance with Marblehead Bylaws Chapter 194, Section 11E. **See Attachment "C" for "Schedule of Fines".**

102. A tarp will be laid down at the base of the seawall during all repair work to capture all construction debris. The tarp will be on the seaward side of the seawall. The tarp will be rolled up and dumped into a disposal trailer as required throughout the work day and will be removed at the end of each work day.

105. Tarps shall be spread and secured over the work area on top of the existing resource area for debris containment and collection during low to medium tides. The tarps and debris will be removed between tides and at the end of workday. At no time are the tarps to be inundated due to rain, tidal or wave action. The tarps are to be removed no less than ½ hour prior to expected inundation. At that time all work is to cease in the area near the resource area.

107. Before any landscape work begins, the applicant shall submit a landscape plan to the Commission for approval. No landscape work may commence until the Commission has approved the landscape plan.

XXX. A minor modification request is required prior to removing the trees noted on the plans. The plans shall identify what trees to be removed and what replacement is proposed.

XXX. Landscaping plans shall show the proposed plan to prevent runoff from entering the ocean over the seawall.

NOI 40-1464 0 Brackett Place – Glover Landing Condominium Trust.

Appeared: Scott Patrowicz, Patrowicz Land Development Engineering

Proposed: Second means of egress for Bldg.21 & site work.

Control Drawing: Site Plan Glover Landing Condominiums Bldg #21 dated 10/24/2020 by Patrowicz Engineering.

Applicant presented plans as provided in application. **No machinery on beach, in the event of major storm forecast, the scaffolding will be removed. The conditions apply to removal of existing means of egress as well, 33, 34, 35, 36, 40, 41, 42, 50, 55, 102, 105**

All members voted to close the hearing. All members voted to issue an OOC with the following special conditions:

33. There shall be no cleaning or rinsing of cement concrete ready-mix trucks, or cement concrete mixing equipment, such that the byproduct of the cleaning or rinsing operation finds its way to any resource area by any means, especially, but not limited to, by means of a storm drainage system (catch basins, pipes, drainage ditches, etc.).

34. To the maximum extent possible, all driveways, terraces, patios or similar ground-level surfaces shall be constructed as permeable surfaces to allow water to infiltrate through their surfaces into the ground on site.

35. All demolition debris shall be removed from the site as soon as possible and not stored within a resource area or a buffer zone. If a dumpster is used to contain debris, the dumpster shall be covered after each work day. The debris shall be properly disposed of in accordance with applicable federal, state and local regulations.

36. All construction material shall be stored outside the resource area and its buffer zone or as far back from the resource areas as possible.

40. By voluntary agreement with the applicant, only organic fertilizers are to be used on the property landward of the resource areas. Fertilizers should not contain pesticides or herbicides; should contain slow release nitrogen and should not contain more than 3% phosphorous. To mitigate chemical runoff, do not fertilize directly before a rainstorm and do not over fertilize. Apply fertilizer in late April and in September (refer to: A Homeowner's Guide to Environmentally Sound Lawn care published by the Massachusetts Department of Food and Agriculture and the booklet, Don't Trash Grass, published by the Massachusetts Department of Environmental Protection). **This condition shall survive this order.**

41. Maintenance pointing and repairs of existing stone masonry walls and concrete walls including the replacement of an occasional missing stone or patching cracks and minor defects in a concrete wall are allowed as a surviving condition to this Order of Conditions. **The property owner shall inform the Conservation Commission in writing at least seven days prior to any proposed repointing or repair work on existing walls.** All dislodged and removed mortar/cement will be immediately contained and removed from the work site to prevent any such material from entering the resource waters. Any future razing, rebuilding or enlarging of the subject wall(s) will require the filing of a new Notice of Intent. **This condition shall survive this order.**

42. The repair/replacement of small sections of damaged caps on seawalls is allowed as a surviving condition. All dislodged and removed caps will be immediately contained and

removed from the work site to prevent any such material from entering the resource waters. Prior to any work, the scope of the proposed repair/replacement must be approved by the Conservation Commission. If the cap on a major length or on an entire wall needs to be repaired/replaced, this requires an NOI. **This condition shall survive this order.**

50. Invasive plants shall not be used nor maintained in the landscape of the project site. This applies to the existing landscape as well as to any proposed landscape. A list of invasive plants in Massachusetts can be found in the latest update of The Evaluation of Non-Native Plant Species for Invasiveness in Massachusetts (with annotated list) produced by the Massachusetts Invasive Plant Advisory Group. For most recent update, visit www.mnla.com or www.newfs.org. **This condition shall survive this order.**

55. Upon completion of the work allowed under this Order of Conditions the applicant shall apply for a Certificate of Compliance (COC) (a) within 30 days after completion of the work or (b) thirty (30) days prior to the expiration date of the original or extended OOC, whichever time comes sooner. If no work was started under the OOC or if some of the work will not be performed, the applicant must still apply for a Certificate of Compliance at least 30 days prior to the expiration of the OOC. The Conservation Commission may require the submission of an "as built" drawing (signed and stamped by a licensed Professional Engineer or licensed Professional Land Surveyor) with the application for the COC. Failure to submit an application for a COC shall result in a fine issued against the applicant in accordance with Marblehead Bylaws Chapter 194, Section 11E. **See Attachment "C" for "Schedule of Fines".**

102. A tarp will be laid down at the base of the seawall during all repair work to capture all construction debris. The tarp will be on the seaward side of the seawall. The tarp will be rolled up and dumped into a disposal trailer as required throughout the work day and will be removed at the end of each work day.

105. Tarps shall be spread and secured over the work area on top of the existing resource area for debris containment and collection during low to medium tides. The tarps and debris will be removed between tides and at the end of workday. At no time are the tarps to be inundated due to rain, tidal or wave action. The tarps are to be removed no less than ½ hour prior to expected inundation. At that time all work is to cease in the area near the resource area.

XX1. No machinery permitted on the beach. The conditions apply to removal of existing means of egress as well.

XX2. In the event of major storm forecast, the scaffolding will be removed..

XX3. The conditions apply to removal of existing means of egress as well.